

HZS50(60)B Concrete Batching Plant

| 11200(00)2 001101010 241011111g 1 14111 | | |
|---|--|--|
| Specification | | |
| Production in theory | 50-60m3/h | |
| Mixing engine | JS1000 | |
| The max grain diameter | 80mm | |
| Feed bin volume | 3×13m3 | |
| Way of transporting | Flat Belt | |
| Feed/aggregate | 3000Kg ±2% | |
| Cement | 600Kg ±1% | |
| Mingled materials | 400Kg ±1% | |
| Water | 400Kg ±1% | |
| Additives | 50Kg ±1% | |
| General power | 110Kw | |
| Weight | 46t | |
| Size | 33.8m×14.8m×10.8m | |
| Discharging height(m) | 3.8 m | |
| Powder tank system(option) | Powder tank volume, quantity, and configuration of | |

Shanghai Longji Construction Machinery Co., Ltd.

Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai

City, China

Post Code: 201100 E-mail: mailto:info@shlongji.com

Tel: +86-21-541-71571 Fax: +86-21-541-71572

| | powder tank accessories varying with customers |
|--|--|
| | demands. |
| Cement screw conveyor(option) | Every Powder pot needs one unit φ219 |
| Configuration Table | |
| Proportioning system PL1600 | |
| Aggregate bin 3x13m3 | 1 set(LONGJIY) |
| Aggregate metering bin | 1 piece(LONGJIY) |
| Weighing sensor | 1 set(America TOLEDO) |
| Output conveyor belt 800mm width (with the clean device) | 1 set(LONGJIY) |
| Cylinder SI-100-300 | 6 pieces(TAIWAN AIRTAC) |
| Vibrator MVE200/3 | 2 pieces(Italy WAM) |
| Vibrator MVE100/3 | 1 piece(Italy WAM) |
| Frame | 1 set(LONGJIY) |
| Aggregate hoist system | |
| Upgrade track | 1 set(LONGJIY) |
| windlass motor | 1 piece(CHINA) |
| hoisting hopper | 1 set(LONGJIY) |
| Mixing system | |
| JS1000A steel structure | 1 set(LONGJIY) |
| Reducer 309 | 2 pieces(CHINA) |
| Motor 22KW | 2 pieces(CHINA) |
| Discharge system | 1 set (Import part assemble in China) |
| Lubricating system | 1 set(BIJUR) |
| Shaft end seal part | 1 set(CHINA) |
| Mixing main building | |
| Main building support leg | 1 set(LONGJIY) |
| Finished receiving hopper | 1 set(LONGJIY) |
| Mixing floor | 1 set(LONGJIY) |
| Metering floor | 1 set(LONGJIY) |
| Stair walkway | 1 set(LONGJIY) |
| Vibrator MVE100/3 | 1 piece(Italy WAM) |
| Host cleaning system SL40A | 1 set(China) |
| Water weighing system | |
| Water weighing box | 1 set(LONGJIY) |
| Water weighbeam | 3 pieces(America TOLEDO) |
| Butterfly valve | 1 set(Italy WAM) |
| Hot water pump | 1 piece(CHINA) |
| Pipeline | 1 piece(LONGJIY) |

Shanghai Longji Construction Machinery Co., Ltd. Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai City, China

E-mail: mailto:info@shlongji.com **Post Code: 201100**

Fax: +86-21-541-71572 Tel: +86-21-541-71571

| Cement weighing system | | |
|--------------------------------------|--|--|
| Weighing bin | 1 set(LONGJIY) | |
| Weighing sensor | 3 pieces(America TOLEDO) | |
| Butterfly valve | 1 piece(Italy WAM) | |
| V1FS250SN-CP101-MIC22-V5V80-BOB02450 | | |
| Vibrator MVE60/3 | 1 piece(Italy WAM) | |
| Additive weighing system | | |
| Additive weighing box | 1 set(LONGJIY) | |
| Pipeline | 1 set(LONGJIY) | |
| Weighing sensor | 1 piece(America TOLEDO) | |
| Butterfly valve | 1 picec(CHINA) | |
| Additive pump | 1 piece(CHINA) | |
| Pneumatic system | | |
| Air compressor | 1 piece(INGERSOLL-RAND/TAIWAN FUSHENG) | |
| Solenoid valve | 1 set(TAIWAN AIRTAC) | |
| Pipe passage system | 1 set(TAIWAN AIRTAC) | |
| Air storage CQG-0.1 | 2 piece(YANTAI) | |
| Electric control system | | |
| Strong electric cabinet | 1 set(LONGJIY) | |
| Weak electric cabinet | 1 set(LONGJIY) | |
| Control console | 1 set(LONGJIY) | |
| Control room | | |

Shanghai Longji Construction Machinery Co., Ltd. Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai

City, China

E-mail: mailto:info@shlongji.com **Post Code: 201100**

Fax: +86-21-541-71572 Tel: +86-21-541-71571